


SIS18 and Accelerators

Peter Spiller



FRS user meeting

29.10.2009

Beam Energy



Operation with U⁷³⁺



- Maximum injected: 4.5×10^9 ions / cycle (effective MTI stacking factor: 13)
- Typical extracted (on target): 2.5×10^9 ions / cycle
- Maximum Unilac current in TK9: ~1.5 mA
- MEVVA source current (U⁴⁺): ~15 mA
- Very stable conditions for about one week during exclusive FRS operation
- Increased average intensity:
 - Ramp rate 1.3 T/s > 4 T/s (New Power Grid Connection)
 - Extraction time: 5 s > 0.5 s
 - Cycle times: 7 s > 2.5 s
 - Factor: ~4

Development Issues for Slow Extraction



- Slow extraction at maximum rigidity (septum length, distance from axis, settings etc.)
- Slow extraction with space charge – debunched (instable) beams
(impedances, simulations, approaching resonance from top etc.)
- Commissioning of KO extraction (hardware available, concentrated work for half a year needed)
- Influence of eddy currents (field measurements ongoing, feed back system)
- Hardt condition, (extraction angle independent from momentum
(set values, experiments ongoing))
- Slow extraction with intermediate charge states (FAIR)


Too little number of synchrotron experts and missing machine development time !

Fast Extraction and Compression



Amorphous MA Cores
Cobalt based

40 kV per Gap



P. Hülsmann, G. Hutter,
H. Klingbeil, W. Vinzenz,
R. Balz, U. Kopf u.a.

Low Duty Cycle System
> Air Cooling


Project completed - cavity installed
Link to the control system outstanding
Fixed frequency operation possible




Original Goal: $\mu Q_f = 6 \text{ GHz}$



SIS18upgrade Program





Injection system for low charged state heavy ions




Charge separator for higher intensity and high quality beams



Power grid connection



Scrapers and NEG coating for pressure stabilization



h=2 acceleration cavity for faster ramping

The SIS18upgrade program: Booster operation with intermediate charge state heavy ions





SIS18 upgrade program



Supported by EU Construction contract:


- **Task 1: RF System**
New $h=2$ acceleration cavity and bunch compression system for FAIR stage 0, 1
(2012)
- **Task 2: UHV System**
New, NEG coated dipol- and quadrupole chambers
(2009)
- **Task 3: Insertions**
Set-up of a „low-desorption“ scraper system
(2009)
- **Task 4: Injection / Extraction Systems**
New, large acceptance injection system plus HV power supply
(2008)
- **Task 5: Beam Diagnostics Systems**
Fast residual gas profile monitor and high current transformer
(2009)
- **Task 6: Injector**
Set-up of a TK charge separator
(2008)

Acceleration of Intermediate Charge State Heavy Ions



- Significant progress with Ta^{24+} and U^{27+} ions due to the upgrade program in comparison with 2001
- Maximum beam energy about 200 MeV/u

Press Release



GSI world wide leading in acceleration of intermediate charge state heavy ions

